BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2015-16/OW/WORK_INDENT19431/CALL-2

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/03/2015-16 Dated: 08-03-2016

Approved Tender Schedule - B

Item No:3

Name of Work: Construction of RO plant at yelahanka old town area in ward No-02 of Yelahanka Sub Division.

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
1	KSRB 2-1.1: Earth work in surface excavation in hard soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No	cum	19.2	220.0	Rupees two hundred twenty and paise zero only
2	KSRB 2-2.2 : Earth work excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5m , in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m. specification, specification. No.	cum	43.04	260.0	Rupees two hundred sixty and paise zero only
3	KSRB 100-1 Loading and unloading ofstone aggregates / sand/ kanker/ Moorum /soil KSRRB M100-1 Placing tipper at loading with front end loader dumpting turning for return trip excluding time for haulged and return trip complete as per specification item No 17.1 page 141 and KSRB M.100.4.1 costof haulage excluding loading and unloading MORTH to a distance of 4.00 K.M	cum	62.24	80.0	Rupees eighty and paise zero only
4	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No.	Cum	8.54	5200.0	Rupees five thousand two hundred and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
5	KSRRB M300-53: construction of embankment with approved material gravel/murrum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murrum, watering charges & compaction by vibratory roller) MORTH specification Page No.	cum	37.8	300.0	Rupees three hundrd and paise zero only
6	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications.	Cum	14.77	6500.0	Rupees six thousand five hundred and paise zero only
7	KSRB 5.2.3 Providing and constructing granite / trap / basalt rubble stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	24.43	4200.0	Rupees four thousand two hundred and paise zero only
8	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:8, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	10.5	4900.0	Rupees four thousand nine hundred and paise zero only
9	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	sqm	27.33	100.0	Rupees one hundred and paise zero only
10	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No.	Cum	16.8	110.0	Rupees one hundred ten and paise zero only
11	KSRB 4-6.7 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour complete as per specifications. Specification	sqm	67.76	210.0	Rupees two hundred ten and paise zer o only
12	KSRB 4-6.10 : Providing and removing centering, shuttering, strutting, propping etc., for chajjas, corbels etc., including edges including cost of all materials, labour complete as per specifications.	sqm	3.12	260.0	Rupees two hundred sixty and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
13	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S. 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	sqm	44.88	900.0	Rupees nine hundred and paise zero only
14	KSRB 4.9.2 providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No.	Quintal	8.26	7000.0	Rupees seven thousand and paise zero only
15	KSRB 15.3.1 : Providing 12mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever reuired smooth rendering, : Providing and removing scaffolding, including cost of materials, labour. Curing complete as per specifications. Page No. 122/ Item No. 15.11/	sqm	62.56	150.0	Rupees one hundred fifty and paise zero only
16	VENTILATORS Hinges 5" heavyduty	Each	4	30.0	Rupees thirty and paise zero only
17	bottom lock nail	Each	10	40.0	Rupees fourty and paise zero only
18	MS Clamps	Each	8	35.0	Rupees thirty five and paise zero only
19	Brass screws 25mm	Each	50	2.0	Rupees two and paise zero only
20	Providing and fixing single shutter glass door of 12mm thick plainToughened glass (Saint Gobain,Modi float).The door is fixed by using any approved make hardware fitting like patch fitting, pivot,Floor machine, locking arrangements and suitable SS door rails withFloral glass etching for 1/3 portion of door area etc complete. The rate includes cost of all materials, labour, hire of tools & machineries, and as per specification.	sqm	14	11500.0	Rupees Eleven thousand five hundred and paise zero only
21	KSRB 14.13.1.: Providing precast chequered mosaic tiles dark shade using ordinary grey cement for steps and flooring, with precast 20mm thick, using marble chips of approved colour 7 to 10 nominal size laid in floors, steps and landings on a bed of 12mm thick cement mortar 1:6, mix, jointed with neat cement slurry mix with pigment to match the shade of tiles curing, rubbing, polishing , oxalic acid wash, wax polish, including cost of materials, labour, HOM machinery complete as per specifications.	sqm	10	950.0	Rupes nine hundred fifty and paise zero only
22	Providing and laying flooring using pre polishing water cut/gang saw 19 mm thick Granite slab over existing cement concrete bed in CM 1:4 at 20mm thick (average) pointed with white cement/ colour pigment etc., complete.	sqm	4.8	2350.0	Rupees two thousand three hundred fifty and paise zero only
23	Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 6000x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc., complete.	sqm	14.8	980.0	Rupees nine hundred eighty and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
24	KSRB 15-17.2: Applying priming coat over new wood surface and / or wood based surface after brushing with wood primer pink paint including preparing the surface after thoroughly cleaning oil, grease, dirt, and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.	sqm	33.44	35.0	Rupees thirty five and paise zero only
25	KSRB 15-17.6: Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.	sqm	33.44	80.0	Rupees eighty and paise zero only
26	KSRB 15.15.1: Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications. with primer.	sqm	33.44	75.0	Rupees and seventy five and paise zero only
27	KSRB 15-16 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. with primer,	sqm	14	80.0	Rupees eighty and paise zero only
28	Supplying and fixing M.S rectangular poles made out of 2 equal angles of 65x656 mm welded together and fixed in CC (1:2:4) with 2 NOS 16 mm dia, M.S hold fast rods each of length 25 cms, including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishing the welded joints with all lead lifts and as per the directions of the Engineer in charge of the work and including providing 2 coats of approved quality paint over one coat of shop painting (excluding cost of earthwork and concrete),	Rmt	20	950.0	Rupees nine hundred fifty and paise zero only
29	Providing and fixing M.S. Block pipe of 38 mm dia, of heavy guage of 14 including removing the bends, cutting the pipe, and fixing pipe in between the two vertical poles (M.S rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting, and scaffolding wherever necessary with all lead and lift as directed by the engineer in charge of work etc, complete including two coats of approved quality paint over one coat of shop paint. No. 265	Rmt	40	300.0	Rupees three hundrd and paise zero only
30	Providing chain link fencing 50 mm size of 8 guage properly stretched between rectangular poles and fixed with suitable bolts & nuts, the free ends shall bed welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the engineer – in charge of work including two coats of approved quality paint over one coat of shop paint.	Sqm	30	840.0	Rupees eight hundred forty and paise zero only
31	POP Sheets corogated roof Sheets nut bolts including labour charges etc complete	Sqm	16.8	4300.0	Rupees four thousand three hundred and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
32	G.I. Roof sheets fixing and complete including labour charges	Sqm	13.5	850.0	Rupees eight hundred fifty and paise zero only
33	Steel Pre fabricates structure with a 14 Guage (3)" each 60 kg including cutting and transportation complete	kgs	400	120.0	Rupees one hundred twenty and paise zero only
34	Point wiring using Copper wire with switch. Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using 1100V grade, COPPER conductor flexible multistrand FRLS PVC insulated, 2X1.5Sq.mm Cable confirming to the GTP without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block complete for each outlet. GROUP A 2.3.1) Short point upto 3Mtr from tapping point to out let via switch box	Point	1 x 2	160.0	Rupees one hundred sixty and paise zero only
35	2.3.2) Medium point above 3Mtr upto 6Mtr from tapping point to out let via switch box	Point	1 x 2	200.0	Rupees two hundred and paise zero only
36	2.3.3) Long point above 6Mtr upto 10Mtr from tapping point to out let via switch box	Point	1 x 2	300.0	Rupees three hundrd and paise zero only
37	Open Conduit System Supplying heavy gauge PVC conduit pipe .....dia .....mm thick confirming to IS 2509 with suitable size bends, junction boxes, adhesive paste etc., and fixing using inverted wood plugs in case of RCC ceiling and RCC wall / stone structure or rawl plugs in case of brick walls and cement plastering the damaged portion using heavy gauge saddles at an interval of 700mm using NF screws.1.1.1) 19/20mm dia 2mm thick	mtr	1+1 20	20.00 45.0	Rupees forty five and paise zero only
38	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand Copper with low conductor resistance single core wire in open or concealed system of wiring with specified IS-694:1990 & confirming to GTP of GROUP -A. 2.5.2) 1.5 sqmm.	Mtr	1+1 30 1+1 20 50	15.0	Rupees fifteen and paise zero only
39	2.5.1) 1 sqmm.	Mtr	50	10.0	Rupees ten and paise zero only
40	2.5.3) 2.5 sqmm.	Mtr	50	30.0	Rupees thirty and paise zero only
41	2.5.4) 4 sqmm.	Mtr	100	62.0	Rupees sixty two and paise zero only
42	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, Finishing with necessary cement plastering complete 1.6.3) 10"x7"x3" (254x178x76mm)	Each	1 x 2	80.0	Rupees eighty and paise zero only
43	1.6.4) 8"x6"x3" (203x152x76mm)	Each	1	65.0	Rupees sixty five and paise zero only
44	1.6.1) 12"x12"x3" (300x300x76mm)	Each	1	150.0	Rupees one hundred fifty and paise zero only
45	Supplying 4mm thick plastic sheet with necessary nitches for fixing switches, regulators etc., and fixing on existing wooden or metal box using N.F. screws.	Sqc m	1225	0.25	Rupees zero and paise twenty five only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
46	Supplying and fixing/replacing of 6/16/32Amps electrical accessories on existing switch board. GROUP A 3.15.1) 6Amps SP Switch	no	1	30.0	Rupees thrity and paise zero only
47	3.15.3) 6Amps 3 way 5 pin Socket	no	1	45.0	Rupees forty five and paise zero only
48	3.15.6) 6 Amps lamp holder	no	3	45.0	Rupees forty five and paise zero only
49	3.15.13) 16/6 Amps combined plug and socket with control switch	no	4	260.0	Rupees two hundred sixty and paise zero only
50	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/ dimmer/telephone socket etc on existing modular switch plate as per IS 3854 and IS 1293 GROUP B 3.7.18) 1000-1200Watts Dimmer	Each	1	400.0	Rupees four hundred and paise zero only
51	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 6.16.1) 5-32Amps SP	Each	1	400.0	Rupees four hundred and paise zero only
52	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3 of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia	No	1	2700.0	Rupees two thousand seven hundred and paise zero only
53	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers. .... 6.7.1) 16Amps	Each	1	100.0	Rupees one hundred and paise zero only
54	Supply patty type fluorescent tube light fitting of 4'-36/40 watts fluorescent tube fitting, made out of M.S sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking type brass contact holders mounted on double fold type sheet base fully wired for use on230 Volts A C Supply including 1No 4'-36/40 Watts fluorescent tube. c) Group 'C' KPWD SR (Ele) 2010-11	Each	5	300.0	Rupees three hundrd and paise zero only
55	Fixing all types and all capacities of fluorescent / false ceiling / spot light / CFL / LED fittings indoor on the wall / ceiling / rafters / girders using 23/0 0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps. 17.7.1) On wall / ceiling / Rafter / Girders	Each	5	90.0	Rupees ninety and paise zero only
56	SHORT POLES: (whereas clearance between Messenger wire and ground is inadequate) a) Supplying and fixing 40mm diat 2.90 thick GI pipe 1.8m long complete with atleast 2 GI pipe 1.8m, long complete with atleast 2 Nos of through bolts 12 mm dia with MS back plate 100x100x6mm dia with eye bolt fixed at top deadeninding messenger wire with masonary patch work etc., complete as per approved drawing (for single phase installations) PWD SR 2007-08	Each	1	500.0	Rupees five hundred and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
57	INSULATED CABLE ON MESSENGER WIRE Using 2 single core wires for a single phase and 4 single core wires for 3 phase. Supplying and stringing PVC insulated and PVC sheathed 650/1100V class aluminium conductor of size supported by 3.15mm (10 SWG) GI messenger wire with two break insulators one at each end of the span with suspenders at intervals of 0.75m. Each suspender shall be of porcelain reel insulator of suitable core through which insulated wire passes(single core or twin core as the case may be) and this reel insulator shall be fixed to the messenger wire using 2mm (No.14SWG) GI wire suitably bent and twisted. Separate reely insulator shall be provided for each wire, the messenger wire shall be ded-ended on the clamp provided to the departmental pole wide item No.4 above.(Page No.56 item No.5 a)Single Phase using 2 Wire e) 16 Sqmm	mtr	55	80.0	Rupees eighty and paise zero only
58	BBMP Approved Rate	mtr	1	946000.0	Rupees nine lakh forty six thousand only
59	BBMP Approved Rate	mtr	1	123000.0	Rupees one lakh twenty three thousand only
60	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site , engaging techinical personal and labour required etc., as per Specification and direction .	Each	1	1800.0	Rupees one thousand eight hundred and paise zero only
61	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) 0 to 50 m	Rmtr	50	300.0	Rupees three hundrd and paise zero only
62	50 to 100 m	Rmtr	50	420.0	Rupees four hundred twenty and paise zero only
63	100 to 150 m	Rmtr	50	450.0	Rupees four hundred fifty and paise zero only
64	150 to 200 m	Rmtr	50	480.0	Rupees four hundred eighty and paise zero only
65	200 to 250 m	Rmtr	50	550.0	Rupees five hundred fifty and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
66	250 to 300m	Rmtr	25	600.0	Rupees six hundred and paise zero only
67	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes)	Rmtr	60	1320.0	Rupees one thousand three hundred twenty and paise zero only
68	Providing and fixing 250mm dia PVC 6 kg/sqcm pressure pipe including jointing and labur charges for laying pipes and as per specification and directions. (BWSSB SR 13-14, P.No.45 I.no.1 of sl.no.11.)	Each	18	1130.0	Rupees one thousand one hundred thirty and paise zero only
69	175 mm dia M.S. Casing cap (P.NO-III, I.NO-85, PRED 12-13 SR)	Each	1	90.0	Rupees ninety and paise zero only
70	M.S. Casing pipe collars 'C' Class (P.NO-III, I.NO-86, PRED 12-13 SR)	Each	15	120.0	Rupees one hundred twenty and paise zero only
71	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH , 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings	No	1	70000.0	Rupees seventy thousand and paise zero only
72	Providing, GI pipes confirming to IS specification of approved make with fittings such as collars bends elbows tees nipples plugs with cuts threads using white lead & threads for joints wherever necessary as per direction including all lead & lift etc,. complete 'A' grade(excluding cost of fittings)b50mm dia GI pipe (SR 13-14 PWD Page No XVII code No 509, 0154)	Rmtr	240	300.0	Rupees three hundred and paise zero only
73	Providing & fixing socket GI (heavy duty collar) (Pwd SR pg xxxviii)	Rmtr	55	80.0	Rupees eighty and paise zero only
74	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and sheathed suitable for working voltage upto 1100 Volts. P. No. 46/ I No. 30-B 4.0 Sqm mm of 36 strands 0.3mm dia Group - A KPWD Electrical SR 2007-08 3/2008-09 4538/19.01.2009 (1x3x4.00 Sqmm PVC cable	Mtr	485	160.0	Rupees one hundred sixty and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
75	Supplying & delivery at site brand new / Essen / Lotus sunsines/Adarsh/ Gk controls best indigenous make combine energy meter-cum-control panel board unit of size 1200 x 600 x 300 mm minimum mechanically strong and vermin and water proof the unit shall have two detachable doors suitable for operation on 3ph, 50Hz, 380/440 volts, AC supply with spring loaded latch locking with a key ribs should be provided inside the door , canopy apron and louvers ventilators shall be provided the combine energy mtr cum control panel board unit suitable for operation on 3ph, 50Hz, 380/440 AC supply shall be consisted etc, completed T panel board shall be fabricated on single unit in the above components panel board for suitable pumpset above components panel board for suitable pumpset above 6.50 HP to 15.00 HP with star delta starter (MR)	No	1	9000.0	Rupees nine thousand and paise zero only
76	Fabricating supplying and mounting MS box of 16 SWG suitable for floor / wall mounting, fully weather proof with provision for better hear description, (providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc, complete box of 21600 sq cm (P.NO-530, I.NO-39 b, BWSSB SR 13-14)	Sqm	22000	0 3	Rupees zero and paise thirty only
77	Providing & Fixing of clamps set and borewell cap to the pump	No	1	450.0	Rupees four hundred fifty and paise zero only
78	Supplying & delivery of brand new best make non return valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark (50mm Gate wheel Valve) (PWD SR 13-14, P.NO XXIV, Sl no. 673)	No	3	1200.0	Rupees one thousand two hundred and paise zero only
79	Supplying and delivery of brand new best make Gate Valve of size 50mm as per IS: 778/84 with latest amendments with ISI mark . 50mm Gate Valve for distributer pipeline 50mm dia (PWD SR 13-14, P.NO XXIV, Sl no. 659)	No	3	1100.0	Rupees one thousand one hundred and paise zero only
80	Providing and fixing of 50mm GI bend to motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No	3	200.0	Rupees two hundred and paise zero only
81	Providing and fixing of 50mm GI Nipple to motor (PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No	3	100.0	Rupees one hundred and paise zero only
82	Providing and fixing of 50mm GI union to the motor ((PWD SR 13-14, P.NO.XXXVIII GI FITTINGS TABLE)	No	3	200.0	Rupees two hundred and paise zero only
83	Labour charges for erection of new /repaired submersible pumpset along with GI pipes (32/50mm) cable (new submersible pumpset if required will be supplied by the department free of cost and released pump set should be handed over to department) including transportation (each length = 6.00m) (P.No - 564, I.No - 3, BWSSB SR 13-14)	L	52	85.0	Rupees eighty five and paise zero only

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
84	Erection of combined panel board meter board with all necessary materials and labour including providing CC 1:3:6 foundation bed etc, Complete for basement out door type. (MR)	No	1	450.0	Rupees four hundred fifty and paise zero only
85	Supplying and fixing miniature circuit breakers/isolators in existing MCB distribution boards using necessary fixing materials and wiring complete as required, 40 to 63 Amps DP (P.NO - 526, I.NO - 13D (a), BWSSB SR 13-14)	No	1	850.0	Rupees eight hundred fifty and paise zero only
86	Supplying and laying of L.T.U.G Cable having aluminiumconductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 KV class 4 core 16 sqmm cable (confirming to IS 1554) (P.NO - 553, I.NO - 10 (d), BWSSB SR 13-14)	Mtr	30+5 35	150.0	Rupees one hundred fifty and paise zero only
87	Digging of trenches of 0.6mm x 0.50 Mtrs wide refilling the trench to the required ground level and consolidating etc,. Complete sutting road surfaces (P.NO - 554, I.NO - 12 (b), BWSSB SR 13-14) in hard soil	Mtr	30+5 35	50.0	Rupees fifty and paise zero only
88	Supplying and fixing Class-A GI Pipe on pole/ wall/drain crossing with necessary clamping arrangements for UG Cable of 1.1 KV class 40mm	Mtr	3	275.0	Rupees two hundred seventy five and paise zero only
89	Supplying and fixing wiring earth electrode for grounding conduits, IC cutouts and other equipments on the meter board using 40mm dia 2.90 mm thick GI pipe 2.5 mtr long buried in a pit,/ the pit should be filled with equal proportion of salt and charocal 150 mm alround the pipe to complete depth the connections from the pipe to the conduit etc, is to be established though GI wire of size as per ISI specification 7.3.3 of ISI 732 using 12mm dia boalts, nuts washers and checknuts etc,. the pipe shall have 16 through holes of 122mm dia	No	1	1500.0	Rupees one thousand five hundred and paise zero only
90	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmmUG cable filled with necessary bitumen/ insulating compound complete with terminals, clamps, bolts nuts and washers etc,	No	1	270.0	Rupees two hundred seventy and paise zero only
91	Supplying shunt capacitor's confirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating No's (MR)	No	1	1350.0	Rupees one thousand three hundred fifty and paise zero only
92	Providing and fixing Gun Metal Gate wheel valve confirming to IS specification of approved make as per direction including all lead and lift etc, Complete 50mm dia	No	4	1450.0	Rupees one thousand four hundred fifty and paise zero only
93	Supplying and fixing of polished wood board made of not less than 15mm thick plank on both sides with planks made out on not more than 2 pieces and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20 x 20 x 2.5 inches	No	1	300.0	Rupees three hundred and paise zero only
94	KSRB 2-1.1 Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications for PVC pipe	Cum	40.5 35.10	270.0	Rupees two hundred seventy and paise zero only

1+1 25.00 × 0.60 × 0.90 = 13.50 cum
1+ 30.00 × 0.80 × 0.70 = 16.20 cum
1+ 10 × 0.60 × 0.90 = 5.40
35.10

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Sri Vasanth R	
				Rate	Rupees in words
95	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.12 item No.3.4.2 b PRED SR 2010-11. 75 mm dia 6 KSC PVC pipe	Rmtr	25	150.0	Rupees one hundred fifty and paise zero only
96	63mm dia 6KSC 30 + 10	Rmtr	50	100.0	Rupees one hundred and paise zero only
97	Providing and installation at site of work 20mm GI pipes including cost of pipes and specials and labur incluidng lowering into trenches, laying ture to line, complete as per direction of Engineer in charge for public taps for motors/pipeline	Mtr	30	120.0	Rupees one hundred twenty and paise zero only
98	laying and jointing GI pipes without earthwork including aligning to line and slope fixing collers elbows tees bends gland cocks and other fittings with cuts and threads whereevere necessary 20mm PRDED SR 2012-13 Item No 3.1.2	Mtr	14	14.0	Rupees fourteen and paise zero only
99	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications Qty vide same as	cum	~~40.5~~	~~70.0~~ Tt No: 94 = 35.10 cum	Rupees seventy and paise zero only

Signature of the contrator

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.